

# Specifications

**803 Waverly 2104 Sq Ft Per Unit – 4 units total**

**3 bedroom, 3 ½ baths**

**2 car attached**

**4th floor roof top terrace**

## Attic

Decked with plywood where needed for additional storage \$0.00

Decking includes a Radiant Barrio "Tech-Shield" to stop heat build up in attic \$0.00

## Ceilings

9' 1<sup>st</sup> floor, 10' 2<sup>nd</sup> floor, 9' 3<sup>rd</sup> floor, 8' 4<sup>th</sup> floor \$0.00

## Climate Control

Honeywell High Performance media filters for better air quality \$0.00

Humidity reducing exhaust fans \$0.00

R-8 Duct work for increased energy savings \$0.00

Dampers for air balancing \$0.00

High efficiency Lennox 14 Seer AC for smooth quiet operation \$0.00

Honeywell digital 4 event 7 day thermostats \$0.00

## Electrical

"GFCI" outlets are installed near all wet areas to prevent accidental shock from small appliances \$0.00

200-amp service installed to handle today's electronics and provide efficient service for upgrading \$0.00

"Arc-Fault" breakers installed in all bedrooms to prevent accidental shock	\$0.00
110 Volt smoke detectors with battery	\$0.00
Ivory Decora (Rocker type) switches used throughout	\$0.00
Copper wiring used throughout home for safe life long reliability	\$0.00
Home is grounded with copper rod driven 6' into the ground to assist in lightning protection	\$0.00
Breaker box has main cut off switch to disconnect entire home from power source	\$0.00
Prewired and trimmed for multi-line telephone usage	\$0.00
Prewired for Cable TV - all outlets are run to a "Smart Panel" in the master closet	\$0.00
Recess cans are included per plan	\$0.00
Overhead electrical service to house from existing power lines	\$0.00
<b><u>Entry</u></b>	
Wood flooring	\$0.00
<b><u>Exterior</u></b>	
Gutters where needed	\$0.00
Cement Board used on all exterior trim 50 Year warranty	\$0.00
<b><u>Fireplace</u></b>	
Marble tile surround	\$0.00
Gas log fireplace	\$0.00
Custom built Mantle	\$0.00
<b><u>Flooring</u></b>	
Oak wood flooring—per plans	\$0.00

Tile in baths  
Carpet in bedrooms  
Oak treads on stairs

### **Foundation**

Slab on grade with beams	\$0.00
Engineer inspected at all phases with letter of approval	\$0.00
Foundation designed and certified by structural engineer	
Soil Sample used to engineer foundation.	

### **Framing**

Corner blocks for added strength	\$0.00
Fire blocking	
Truss hangers and joist hangers to ensure stability	\$0.00
Plywood tongue and grove decking	\$0.00
Engineered floor trusses for second floor on 19" Centers	\$0.00
Laminated beams where needed for structural support	\$0.00
Roof and Ceiling framed using 2x6 and 2x8	\$0.00
Hurricane straps throughout for a safe home in all weather	\$0.00
Plywood used on 100% of exterior for a "Super Strong" structure	\$0.00
Steel anchor bolts are used to attach base plate to foundations	\$0.00
All framing on 16" centers using top grade materials	\$0.00
DOW Sill under all exterior base plates to eliminate draft	\$0.00

Window wrap on top and sides of windows	\$0.00
---	--------

### **Garage**

Steel door	\$0.00
------------	--------

Garage door opener with remotes	\$0.00
---------------------------------	--------

Garage door opener wall switch	\$0.00
--------------------------------	--------

Wall paint flat	\$0.00
-----------------	--------

### **Greatroom**

Surround sound prewire (equipment not included)	\$0.00
---	--------

Oak wood flooring	\$0.00
-------------------	--------

### **Insulation**

Exterior walls of improved living areas insulated with blown fiber to a thickness of 3.5 inches, which yields an R-Value of 13 and prevents drafts along with superior sound reduction	\$0.00
--	--------

Recess cans are completely sealed to prevent outside air from coming in	\$0.00
---	--------

Poly Seal all exterior openings and wire openings to attic	\$0.00
--	--------

DOW Sill under all exterior base plates to eliminate draft	\$0.00
--	--------

R-8 Duct work and plenum sealed with fiber reinforced mastic	\$0.00
--	--------

Walls in other areas of the home insulated with fiberglass batts to a thickness of 6 inches, which yields an R-Value of 19	\$0.00
--	--------

Ceilings in improved living areas insulated with fiberglass batts to a thickness of 12 inches, which yields an R-Value of 30	\$0.00
--	--------

### **Kitchen**

Granite counters	\$0.00
------------------	--------

Cabinets	\$0.00
Oak wood flooring	\$0.00
Appliances include: cooktop, oven, microwave wine fridge, & refrigerator all stainless steel	
Tile backsplash to coordinate with counters	\$0.00

### **Master Bath**

Marble counters	\$0.00
Cabinets	\$0.00
Separate shower	\$0.00
Tile flooring	\$0.00
Glass shower door	\$0.00
Acrylic tub	\$0.00
Under mount sinks with fully polished edges	\$0.00

### **Master Bdrm**

Single crown	\$0.00
Carpet	\$0.00

### **Paint**

Trim paint satin enamel	\$0.00
Paint for all walls - flat	\$0.00

### **Plumbing**

Pvc drains and vents	\$0.00
1 50 gallon gas water heaters	\$0.00
Steel bath tubs in secondary baths	\$0.00
New sewer connection	\$0.00
Water pipe is PEX for added life and leak protection	\$0.00
Gas lines are installed using "Black Steel" piping for a lifetime of leak free usage	\$0.00

### **Powder room**

Under mount sinks with fully polished edges	\$0.00
Oak wood flooring	\$0.00
Marble counters	\$0.00

### **Roofing**

Ridge vent and soffit vents to keep the attic cool to lower utility bills	\$0.00
Decked with 100% plywood	\$0.00
Decking includes a Radiant Barrio "Tech-Shield" to stop heat build up in attic	\$0.00
Vented soffit material to increase attic air	\$0.00
30 year asphalt shingles	

### **Secondary Baths**

Steel covered enamel bath tubs in secondary baths	\$0.00
Drop in sinks	\$0.00
Marble counters	\$0.00
Tile flooring	\$0.00
Culture marble tub surround	\$0.00

### **Security**

Security system with all accessible openings monitored, includes 1 keypads, a motion detector, and a glass break sensor.	\$0.00
--	--------

### **Sheetrock**

Ceiling to have 1/2 inch sheetrock	\$0.00
No sheetrock is used on the exterior	\$0.00
Hardi Backer used in wet areas	\$0.00
All corners are bull nosed for a soft sophisticated feel	\$0.00
Walls to have 1/2 inch sheetrock	\$0.00
Texture is applied to the walls and ceiling for an elegant look	
Level 3 finish is used to reduce the appearance of the sheetrock joints	\$0.00

All joints are "Tape and Floated" for a smooth even look	\$0.00
Garage to have 5/8 inch fire rated sheetrock	\$0.00

**Stairs**

Oak treads with painted risers	\$0.00
--------------------------------	--------

**Trim Material**

Interior trim to be paint grade	\$0.00
---------------------------------	--------

**Utility**

Floor drain to exterior	\$0.00
Tile flooring	\$0.00
Humidity reducing exhaust fans	\$0.00
Water connection and drain for washing machine	\$0.00
Gas connection for dryer	\$0.00

**Walks and Drives**

Concrete	\$0.00
----------	--------

**Windows**

Low "E" double pained windows for insulation and UV protection	\$0.00
Windows are "Energy Star" certified to meet today's conservation requirements	\$0.00

***Plans and specifications are not a contract between a builder and a homeowner. They may change at anytime and are not agreed upon until signed in a contract by both parties.***

---

<i>Homeowner</i>	<i>Date</i>
------------------	-------------

---

<i>Homeowner</i>	<i>Date</i>
------------------	-------------

---

<i>Diamond Custom Homes, Inc.</i>	<i>Date</i>
-----------------------------------	-------------

---